

● The **Electrical work**, is as follows:

1. Power to equipment, which is removed, is demolished.
2. Power for new equipments is provided
3. Lighting and receptacles are provided for the Hermann Building cooling Tower.

A new 4160 Volt feeder is provided to the Engineering 1 Building to handle the increased load associated with the new chillers.